APPENDIX D PROJECT QUALITY ASSURANCE SUMMARY

D. PROJECT QUALITY ASSURANCE SUMMARY

This appendix presents the actions and methodologies undertaken to meet the quality assurance (QA) goals for the project. These goals were established in the Facility-Wide Sampling and Analysis Plan for the Ravenna Army Ammunition Plant (USACE, 1996) and the Phase II Remedial Investigation (RI) Sampling and Analysis Plan Addendum for Winklepeck Burning Ground (USACE 1998). These were implemented through project-specific procedures and requirements, the Science Applications International Corporation (SAIC) QA Program, and the U.S. Army Corps of Engineers - Louisville District QA requirements. A large proportion of project QA was focused on field and analytical laboratory activities and project administration.

D. 1 FIELD QUALITY ASSURANCE

D.1.1 Readiness Review

Field QA was initiated at the Ravenna Army Ammunition Plant (RVAAP) WBG Phase II RI readiness review held at the SAIC Oak Ridge offices on April 15, 1998. The purpose of the readiness review was to ensure that (1) all project documents and procedures were approved, controlled, and properly distributed; (2) all assigned personnel were trained or a schedule was established to conduct training; (3) the mobilization and site logistics were established; (4) the laboratories were ready to accept samples; (5) all other subcontractors were ready to begin work; and (6) the QA system was implemented. All elements of the readiness review were completed prior to initiating field activities.

D.1.2 Procedures

Standard operating methods for field activities performed during the Phase II RI at WBG are incorporated into the governing documents for the project. The Facility-Wide Sampling and Analysis Plan (USACE 1996) describes the overall approach and methodologies to be used for projects at RVAAP, and the Phase II Remedial Investigation Sampling and Analysis Plan Addendum for WBG (USACE 1998) details project-specific requirements for field implementation. These documents were reviewed and approved by USACE - Louisville District, and reviewed and commented on by the Ohio EPA prior to implementation. Clarifications and/or planned deviations from these methods have been documented as field change orders (FCOs), and variances have been documented as non-conformance reports (NCRs). Copies of the FCOs are attached to this Appendix.

D.1.3 Training

Field team personnel were trained in all procedures applicable to their assigned tasks. Training was accomplished by combinations of classroom lectures, reading assignments, and on-the-job training. Surveillance performed by an SAIC QA specialist provided assessments of worker proficiency and training effectiveness.

Training was documented by the completion of training records. Performance documentation was completed in the field by the QA specialist after observing successful implementation of a procedure by a field team member. Copies of training records and surveillance reports were

maintained in the project file and/or in the SAIC Central Records Facility (CRF). Copies of training records required for OSHA and DOT compliance also were maintained in the field.

D.1.4 Equipment Calibration

Various types of Measuring and Testing Equipment (M&TE) were used during the field investigation. All M&TE was categorized, assigned unique identifiers, and listed in an inventory in the M&TE logbook. Last and next calibration recall dates were also recorded. As appropriate, instruments were calibrated daily according to the manufacture's instructions. Only equipment and standards having verifiable traceability to nationally recognized standards were used for calibration. Daily calibration activities and results were recorded in the M&TE logbook as well as source information for all calibration standards and reagents.

D.1.5 Quality Control Samples

Field quality control (QC) samples, including trip blanks, equipment rinsate blanks, source water, field duplicates, and field QA splits were collected as specified in the Phase II Remedial Investigation Sampling and Analysis Plan Addendum for WBG (USACE 1998) pertaining to contractor chemical quality control. Implementation of the Contractor Chemical Quality Control program was observed by the SAIC QA specialist. Field QC data and analysis of QC results are presented in Appendix F.

D.1.6 Field Records

Field data, observations, activities, and information were recorded in pre-formatted, bound field logbooks. The use of structured logbooks ensured that all necessary data were entered consistently. Logbook entries were checked for accuracy and completeness by independent reviewers. Critical and/or contract-required original records (e.g., sampling forms) were recorded in duplicate using carbonless paper. Other field records which were collected and likewise maintained included equipment/material certifications, boring logs, and air-bill forms.

D.1.7 Surveillance and Audits

Surveillance of operations at RVAAP during the Phase II RI at WBG was conducted by SAIC. This surveillance assessed technical and quality-related activities including surface soil/sediment sampling, monitoring well installation, purging, and sampling, equipment decontamination, training and health & safety practices, and field record review. The WBG Phase II RI was also the subject of an internal QA audit, which reviewed records management and conformance with project document review practices and personnel training/qualification. The results of the surveillance and audit are documented as a QA Surveillance Report and QA Audit Report, copies of which are included in the project file. Discrepancies identified during these reviews are documented as NCRs.

D.2 ANALYTICAL LABORATORY QUALITY ASSURANCE

SAIC subcontracted an analytical laboratory, Quanterra, to perform chemical analysis for the WBG Phase II RI. The selected laboratory was qualified by the USACE - Missouri River Division (MRD). In addition, this laboratory was technically audited by SAIC prior to contract award.

98-173P(doc)/072399 **D-4**

D.2.1 Readiness Review

Laboratory QA activities were initiated during the readiness review. The readiness review ensured that (1) governing documents and approved analytical methods were controlled and properly distributed; (2) the laboratory was scheduled and ready to conduct the analysis; (3) logistical coordination was established between the laboratory and the field team; and (4) laboratory QA programs were consistent and compatible with the project requirements.

D.2.2 Procedures

Prior to initiation of analytical support for the WBG Phase II RI, Quanterra and SAIC reviewed and negotiated a contract based on a comprehensive Statement of Work (laboratory SOW). The laboratory SOW represented and referenced project-specific requirements, including the parameters to be measured, the analytical methods to implement, adherence to USEPA SW-846 protocol, project quantitation goals (sensitivity), and data deliverables required. All laboratory comments and questions were resolved before analytical work proceeded.

D.2.3 Laboratory Quality Control

To document laboratory data quality and to measure the quality of the analytical process, laboratory quality control samples and data verification/validation were employed. The results of laboratory QC are discussed in the project data quality assessment (Appendix F). Analytical results of laboratory QC samples are included in the project file and form the basis of the data validation and verification process.

D.2.4 Laboratory Documentation

The laboratory maintains comprehensive information regarding the entire analytical process. The laboratory delivered summary data packages and electronic deliverables consistent with those identified in the EPA SW-846 protocol to SAIC for validation and verification. Laboratory QC sample analyses were cross-referenced to the appropriate environmental field sample analyses in the laboratory deliverables.

D.2.5 Data Verification/Validation

Analytical data generated during this project have been subjected to a rigorous process of data validation and verification. Criteria were established against which the analytical were compared and from which a judgment was rendered regarding the acceptability and qualification of the data. Upon receipt of data packages from each laboratory the information was subjected to a systematic examination following standardized checklists and procedures to ensure content, presentation, administrative validity, and technical validity. All deficiencies in the data were documented through the Analytical Data Nonconformance Report (ADNCR) program.

D.3 QUALITY ASSURANCE DOCUMENTATION

Primary methods for documenting QA during the WBG Phase II RI include the completion of Field Change Orders (FCOs) and Nonconformance Reports (NCRs). Copies of FCOs completed during the investigation are included at the back of this appendix. Copies of NCRs are on record in the SAIC RVAAP project file.

98-173P(doc)/072399 **D-5**

D.3.1 Field Change Control

Field changes were implemented during the RI to address changes to the approved Facility-Wide Sampling and Analysis Plan for the Ravenna Army Ammunition Plant (USACE 1996) and the Phase II Remedial Investigation (RI) Sampling and Analysis Plan Addendum for Winklepeck Burning Ground (USACE 1998) necessitated by field conditions. Field changes implemented were all minor in scope, providing clarification or refinement in the procedural approach to a specific field activity. All FCOs were reviewed and approved by designated representatives of USACE - Louisville District prior to implementation. None of the FCOs resulted in an adverse impact to project quality, schedule, or scope. Copies of the eleven approved FCOs are included in Attachment D.1.

The purpose of most of the FCOs was to request and document changes to the approved plans. There were eleven issues not anticipated or not identified during project planning. Five of these were clarifications or corrections to planned methodologies. For example, FCO-004 provides clarification of SAP Addendum requirements for the number and placement of geotechnical soil samples in Section 4.2.2.4. The remaining six FCOs represented revisions to a planned method or to a strategy for locating samples. For example, FCO-007 and -011 amended the SAP Addendum, Section 4.2.2.1, to allow analysis of several soil samples for propellants nitrocellulose, nitroglycerine, and nitroguanidine.

D.3.2 Nonconformance Reports

To identify and correct conditions adverse to quality as described in the field and laboratory QA plans, NCRs, ADNCRs, and corrective action reports (CARs) were completed, as necessary. Between project initiation and December, 1998, 2 NCRs, 1 ADNCR, and 0 CARs were completed. During the WBG Phase II RI, NCRs were initiated both during the QA surveillance and by the laboratory coordinator when a nonconformance occurred. The ADNCR and both NCRs initiated during the project have been corrected and/or closed.


A summary of the actions or items that warranted the initiation of ADNCRs and NCRs included:

- Six samples were collected for metals and explosives analysis, but based on field observations indicating organics contamination, the USACE PM requested the samples be analyzed for VOCs and SVOCs instead. As the samples were not originally planned for organic analyses, the samples were collected from composited material and the sample jars subsequently taped. This is in conflict with standard requirements for the collection of VOC samples, and the tape was removed from the jars. The subject samples were sent to the lab for VOC analyses as requested by the client. The analytical data went through the standard validation process. While compositing of samples may have allowed some organic compounds to volatize, the results would have been flagged "J" (estimated). The taping of the sample jars would not have impacted the results other than elevated toluene readings. As such, it was determined that the data was usable and did not need to be rejected.
- An inconsistency was noted between the EDD and Form 1 for sample WB0750 (2,4-DNT). EDD was correct, and corrected Form I's were prepared.
- Thallium values reported for Phase II WBG soils and sediments were inaccurate. The MDL used to report the data was 0.5 mg/kg wet weight; it should have been 0.65 mg/kg dry weight. The lab needs to correct all affected data and re-report this data to the project. The

98-173P(doc)/072399 **D-6**

lab must also document that the other metal data has not been impacted due to any similar systematic causes. The laboratory has resubmitted corrected values on a dry weight basis. There is no impact to the report discussion or conclusion based on this change.

D-7



| Field Change Hequest (FCR) |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| FCR NO. 001 DATE INITIATED 4.14.98 |
| PROJECT RVAAP PHASE II RI - WINKLEPECK BURNING GRAND |
| CONTRACT NO. DACAGZ-94-D-0029 |
| REQUESTOR IDENTIFICATION |
| NAME S. SELECMAN ORGANIZATION SAIC PHONE 423.481.861 TITLE PROJECT MGR - SAIC SIGNATURE |
| BASELINE IDENTIFICATION |
| BASELINE(S) AFFECTED O COST O SCOPE O Milestone @ Method of Accomplishment AFFECTED DOCUMENT (TITLE, NUMBER AND SECTION) Phas IT R.I. SAMPUNG ANALYSIS PLAN ! DESCRIPTION OF CHANGE: IN TABLE 1-1 OF GAPP, THE NUMBER OF "USACE OF SPLIT SAMPLES" FOR GRONDINATER/ SURFACE WATER SHOULD BE ZERO (B) ON EVERY LINE, EXCEPT FOR PCBS/PESTICIDES (I) AND CHANIDE (I). TABLE 1-2: "USACE OF SPLIT SAMPLES" FOR GRONDWATER, SHOULD BE CHANGED FROM ZETRO TO ONE (I) EACH FOR THE ANALYTES SHOULD, FER. ATTACHED MARK-UP. |
| JUSTIFICATION: CORRECTS AN OVERLOOKED ERROR IN THE GAPP TABLES. |
| · · |
| IMPACT OF NOT IMPLEMENTING REQUEST: INCORRECT NUMBERS & TYPES OF QUESTION OF AMELYZED. |
| PARTICIPANTS AFFECTED BY IMPLEMENTING REQUEST: USACE SPLIT LABORATORY, SAMPLE MGR. |
| COST ESTIMATE (\$) NA ESTIMATOR SIGNATURE DATE |
| PREVIOUS FCR AFFECTED OYES ONO; IF YES, FCR NO. |
| CLIENT PROJECT MANAGER |
| D-11 |

Table 1-1. Phase II RI Site Background, RVAAP - Sampling and Analytical Requirements

| | | 1 | | | | | | | |
|-----------------------------------------|----------------------------|----------|---------------------------|--------|----------|------|---------|-------|----------|
| | | | | | | | | USACE | OEFA |
| | | | Pie id | Site | | | Total | \$ | <u>ځ</u> |
| | | Yes | Duplicate | Source | Sampler | Trip | A-E | Spik | Spilit |
| | Methods | Samples | Samples | | Kinstict | | Samples | | |
| | | Seils | Sails/Sediments | | ļ | | | | |
| graph. | CW.944 R760A | 2 | - | | , | _ | 11 | - | - |
| Volgile Organics, TCL | 200 270 2100 | 77 | ~ | · | , | , | 64 | m | • |
| Semivolatile Organics, TCL | 3W-540, 84./UB | ; | | | | | 2 | _ | |
| Pesticides/PCBs, TCL | SW-846, 8081 | 2 | - | | | | | - | |
| Marie TAL | SW-846, 6010A/7471 | 59 | 9 | | | | G | , | |
| 1 | SW-846, 9013 | 65 | 9 | • | · | | 2 | - | |
| Cymnos | SW-846 8330 | 0 | 0 | ' | • | • | ٥ | 0 | |
| Explosives | | 3 | 2 | | | , | -1 | | • |
| Total Organic Carbon (TOC) | | 2 | - | | | | ; | | ٠ |
| Grain Size, Moisture Content, Atterburg | ASTM DA22, D2216, D4310 | 4 | ١ | • | , | , | ; | | |
| Bulk Density, Porosity | ASTM D453, | • | , | , | • | , | ** | | ı |
| | EM1110-2-1906 | | | | | | | / | |
| | | Greendwa | Greundwater/Surface Water | | | | | / | |
| Volaile Organics, TCL | SW-846, \$260A | 2 | - | 2 | | - | • | 0 | |
| Semivabelle Organica, TCL | SW-846, \$270B | 2 | - | 7 | | | | | :/ |
| Paristales/PCBs. TCL. | SW-846, BO\$1 | 2 | _ | 2 | | • | | - \ | 1 |
| TALL CONT. | SW-846, 5010A/7470 | n | 2 | 2 | - | | 31 | 0 | • |
| Michael (World), 1781 | SW-846, 6010A/7470 | 2 | - | 7 | • | | = | 9 | • |
| Metas (dissoved), 1 AL | CW-846 9013 | 3 | ~ | + | - | - | 2 | 7 | \ |
| Cyanide | Con, 616 | ٤ | _ | 2 | - | | 6 | 0 | • |
| Explosives | 5W-040, 6230 | | | | | | | | |

1 Site source waters = one potable water source and one ASTM water supply lot for the project.

| _ |
|-------------------|
| 2 |
| . |
| ₹ |
| 5 |
| 2 |
| 3 |
| 묫 |
| × |
| = |
| a |
| 꼰 |
| Ŧ. |
| É . |
| 3 |
| ₹ |
| - |
| ¥ |
| pling an |
| 100 |
| £ |
| 풀 |
| E |
| = |
| 2 |
| 7. |
| <u> </u> |
| 7 |
| _ |
| - |
| 5 |
| = |
| Ŧ. |
| Ž |
| 묫 |
| 2 |
| Ğ |
| <u></u> |
| 五 |
| 2 |
| Ē |
| 2 |
| |
| 24 |
| X |
| L |
| 7 |
| Ž |
| ₹ |
| 5 |
| - |
| |
| X |
| 2 |
| IRI |
| e II RI |
| Be II RI |
| see 11 R |
| Phase II R |
| Phase II R |
| 1. Phase 11 R |
| Phase II R |
| t 1-2. Phase 11 R |
| t 1-2. Phase 11 R |
| t 1-2. Phase 11 R |
| 1. Phase 11 R |

| | | P.27. | Field Deplicate | Saurce Saurce | Sampler | Trip | Total A-E | USACE Spin | Ohio EPA Spili |
|----------------------------|--------------------|----------|--------------------|------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------|---------------|----------------------|
| Paracter - | meineda | Sett | Seils/Sediments | | NAME OF THE OWNER | | | | |
| Semivolatile Organics, TCL | SW-846, 8270B | •• | 1 | ٠ | | | 6 | - | • |
| Metals, TAL | SW-846, 6010A/7471 | 116 | 12 | • | • | • | 128 | 7 | • |
| Cyanide | SW-846, 9013 | 911 | 12 | • | • | • | 128 | 7 | • |
| Embasives | SW-846, 8330 | 112 | 12 | • | 1 | • | 124 | 9 | • |
| | | Cr | Greandwaler | | | | | | |
| Volatile Organics, TCL | SW-446, \$260A | 6 | | • | , | 3 | 13 | 1 | |
| Semivolatile Organics, TCL | SW-446, 8270B | 6 | 1 | • | • | • | 10 | - ø | |
| Metals (total), TAL | SW-446, 6010A/7470 | 6 | - | • | | | Q. | ا کام | |
| Metals (dissolved), TAL | SW-446, 6010A/7470 | 6 | - | , | • | • | 01 | # | \. |
| Cyanide | SW-446, 9013 | 8 | 2 | , | , | • | | - 9 | - |
| Fundatives | SW-446, 8330 | 6 | l. | | • | • | 10 | 7 | |
| | | | | | | | | | |

98-003P(WPD)(QAPP-ADD)/012098

| | ried Charge nequest (| runj | |
|------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------|-----------------------|---------------------------------------|
| FCR NO. 002 | DATE | E INITIATED_ | 4.14.98 |
| PROJECT RVAAP PHASE I | R.I WINKLE PECK BURNING | GROND | |
| CONTRACT NO. DACA 62 - 9 | 4-D-6029 | | |
| REQUESTOR IDENTIFICATION | 1 | | |
| NAME S. SELECTIAN OF TITLE PROJECT MGR. SIC | RGANIZATION SAIC I | PHONE 423. | 481.8761 |
| BASELINE IDENTIFICATION | · · · · · · · · · · · · · · · · · · · | | |
| BASELINE(S) AFFECTED OC AFFECTED DOCUMENT (TITLE DESCRIPTION OF CHANGE: | , NUMBER AND SECTION <u>) Fit</u> | ASE II R.I. | SAMPLING, AND |
| 1. On page 4-1, text should re 2. On page 4-32, text should RVA AP", not 3. Comments on human & hea be incorporated into the Phase | read, "Tourteen monitoring well read," In addition two. | samples of s | lalled "-not Love, |
| JUSTIFICATION: Conditions- office of Ohio EPA-CO | for in hali-, held work excepts & derifies exist | reviewed hy final. | by N.E. Distinct SAP. |
| IMPACT OF NOT IMPLEMENTIN | G REQUEST: Potential for | field errors. | |
| | | | |
| PARTICIPANTS AFFECTED BY I | MPLEMENTING REQUEST: | | · · · · · · · · · · · · · · · · · · · |
| COST ESTIMATE (\$) NA | STIMATOR SIGNATUREPHONE | DATE | *** |
| | | | |
| PREVIOUS FCR AFFECTED O | YES ONO; IF YES, FOR N | O | |
| CLIENT PROJECT MANAGER _ CLIENT QA SPECIALIST_ | Jel Jul | | E4-21-58 |
| SAIC H&S MANAGER SIGNATU | RE (IF APPLICABLE) | DATE _ | DATE |
| | | | |

| FCR NO. 003 DATE INITIATED 4.14.98 |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PROJECT RVAAP Phase IR. 1 WINKLEPECK BURNING GROUND |
| CONTRACT NO. DACA 62 - 94-D-0029 |
| REQUESTOR IDENTIFICATION |
| NAME S. SELECMAN ORGANIZATION SAIC PHONE 423.481.8761 TITLE PROJ. MANAGER SIGNATURE |
| BASELINE IDENTIFICATION |
| BASELINE(S) AFFECTED O COST & Scope O Milestone & Method of Accomplishment AFFECTED DOCUMENT (TITLE, NUMBER AND SECTION) Prese I R.I. SAMPLING AND DESCRIPTION OF CHANGE: SECTION 4 SPECIFIES WELL PURGING WILL BE ACCOMPLISHED VIA MICRO-PURGING ACCORDING TO DEPA GUIDANCE. INSTEAD, WELLS WILL BE PURGED PRIOR TO SAMPLING USING CONVENTIONAL PURGING METHODS (e.g., SUBMERSIBLE, MON-DEDICATED, MEDIUM-CAPACITY PUMPS). |
| JUSTIFICATION: COSTS FOR MICRO-PURGE EQUIPMENT NOT BUDGETED IN ORIGINAL LOST PROPOSAL |
| |
| MPACT OF NOT IMPLEMENTING REQUEST: ADDITIONAL COST OF ~ \$30,000 TO ACQUIRE LOW-FLOW PUMPING EQUIPMENT, TUBING, FITTINGS, AND CONTROLLERS. |
| PARTICIPANTS AFFECTED BY IMPLEMENTING REQUEST: FIELD SAMPLING TEAM. |
| COST ESTIMATE (\$) ESTIMATOR SIGNATURE DATE |
| PREVIOUS FCR AFFECTED O YES ONO: IF YES, FCR NO. |
| CLIENT PROJECT MANAGER CLIENT QA SPECIALIST DATE SAIC H&S MANAGER SIGNATURE (IF APPLICABLE) DATE DATE |

| Field Change Order (FCO) |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| MODIFICATION NO DATE 4.24.90, WORK AUTHORIZATION |
| TYPE OF CHANGE CLARINCETUM PRIORITY OFMERGENCY OUROSTIC |
| CYWP NO. CWBS NO. |
| REQUESTER IDENTIFICATION |
| NAME K. DOMINIC ORGANIZATION SAIC PHONE 937 431 2239 |
| TITLE FIELD MANAGER_ SIGNATURE MANAGER_ L. Dominic |
| BASELINE IDENTIFICATION , |
| BASELINE(S) AFFECTED O COST O SCOPE O MILESTONES OMETHOD OF ACCOMPLISHMENT |
| PROGRAM SERVICE ORDER NO REVISION NO REVI |
| DESCRIPTION OF CHANGE TABLE 4-3 AND SECTION 4.2.2.4 PHONE |
| DESCRIPTION OF CHANGE TABLE 4-3 AND SECTION 4.2.2.4 PHONE Call for the following BACKGROUND geotechnical sampling: 1 Grab samples - 0-1' - 6 Errors are present in the text and tables, and are clarified, 1 3 grab + shelby turns - 1-3' - 6 corrected, and modified in follows: Grab samples - 0-1' - 5 Shelby time - 8 held in 1 grab samples - 0-1' - 5 3-12' - 10: |
| shelby tobes - 8 total taken in concrete this and 3-12'-10. |
| JUSTIFICATION Allows a greater number of characterization Samples at depth, where |
| The contest reducadant Tio |
| |
| NOTE: These samples will be collected in the bedrock borings out! |
| |
| MPACT OF NOT IMPLEMENTING REQUEST Incomplete seatechnical characterization of u- |
| MPACT OF NOT IMPLEMENTING REQUEST Irremplete geotechnical characterization of the deeper subsurface (agrifus + agritund) Intrologies |
| |
| |
| |
| PARTICIPANTS AFFECTED BY IMPLEMENTING REQUEST Well Site sampling team. |
| |
| |
| COST ESTIMATE \$ ESTIMATOR SIGNATURE |
| |
| PHONE DATE PREVIOUS FC AFFECTED O YES PAGE |
| APPROVAL APPECIED O'YES DANO |
| PROJECT MANAGER CICHERUS (bd /) |
| QAS REVIEW DATE |
| TIME FROM INITIATION TO ACTION |
| D-16 |
| L |

| Field Change Order (FCO) |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| MODIFICATION NO DATE WORK AUTHORIZATION |
| TYPE OF CHANGE CLASSICATION PRIORITY O EMERGENCY O URGENT PROUTINE |
| ADS NO CYWP NO CWRS NO. |
| REQUESTER IDENTIFICATION |
| NAME K DOMINIC ORGANIZATION SAIC PHONE 937.431.2239 |
| TITLE Fuld Cos Mgs SIGNATURE Killy - L Dominic |
| BASELINE IDENTIFICATION |
| BASELINE(S) AFFECTED O COST O SCOPE O MILESTONES OMETHOD OF ACCOMPLISHMENT PROGRAM SERVICE |
| ORDER NO REVISION NO CAM SIGNATURE |
| DESCRIPTION OF CHANGE Sections 4.4.1. and 4.4.2.1 Surface water samples collected from WBG (Marc's Pend) will be analyzed as follows filtered samples for TAL metals, equinde: also untiltered voc, svoc, at explosive samples Background surface water samples will not be filtered prior to analysis. |
| s some water surplies will not be filtered prior to analysis |
| |
| JUSTIFICATION Alleviation ambiguites in section 4.4 about which samples of surface water are to be filtered prior to analysis. |
| MPACT OF NOT IMPLEMENTING REQUEST Sending filtered and unhitered samples for metal to cyanide for way surface water sample will cause cost growth and is unnecessary for meeting project objectives. |
| PARTICIPANTS AFFECTED BY IMPLEMENTING REQUEST Field Sampling hear; sample manager. |
| COST ESTIMATES ESTIMATOR SIGNATURE |
| COST ESTIMATE \$ ESTIMATOR SIGNATURE |
| PHONE DATE PREVIOUS FC AFFECTED O YES ONO |
| APPROVAL |
| PROJECT MANAGER SIGNATURE |
| QAS REVIEW DATE |
| TIME FROM INITIATION TO ACTION |
| D-17 |

| гэр сос | <u>a006</u> | Q006 Q007 | Q006 Q007 | Q006 Q007 | Q006 Q007 | Q006 Q007 | Q005 | Q005 | ۵005 | Q005 Q007 | Q005 Q007 | 0005 | 0005 | 2005 | 9000 | 2006 | 0000 | Q008 | Q008 | Q005 | 0005 |
|----------------------|-------------|--------------|--------------|--------------|--------------|--------------|---------|---------|---------|--------------|--------------|---------|---------------|--------|---------------|---------|---------|---------|---------|---------|-----------|
| RDX | | | 0 | | | | Ť | | Ť | | | Ť | Ť | Ť | Ť | Ť | Ť | 0 | Ť | ľ | Ĭ |
| TNT | | | | | | | | 0 | Н | | | 6 | 0 | 0 | | 0 | 0 | 0 | 0 | Н | \dashv |
| Geotech | | | × | | | | | _ | | | × | | × | | | | | Т | | | \exists |
| 201 | | | | | | | | | П | | | ┪ | | П | П | П | - | | | | ╗ |
| PCB/Pesticides | | | | | | | Г | | | | | Т | Т | | П | Т | | | П | | \neg |
| VOCs | | | | | | | | | | | | | | | | | | П | П | | ٦ |
| SAOCS | | × | | | | | Г | X | | | • | Г | | | П | | | | | × | \neg |
| СИ | × | × | × | × | × | × | × | X | × | × | × | × | X | × | × | × | × | × | × | × | |
| TAL Metals | × | × | × | × | × | × | × | × | × | x | × | × | X | × | × | X | X | × | × | × | ┫ |
| Explosives | × | × | × | × | × | × | × | X | × | × | × | × | X | × | × | × | × | × | × | × | × |
| Field EXP. | × | × | × | × | × | × | × | X | × | × | × | × | × | × | × | × | X | × | × | | ┨ |
| Matrix | SO | so | so | so | so | so | SO | SO | SO | so | os | SO | so | SO | ၀ွ | SO | SO | SO | SO | SO | စ္တ |
| Time | 1112 | 1023 | 0858 | 0918 | 1356 | 1315 | 1541 | 1450 | 1344 | 1245 | 1358 | 0957 | 1021 | 1035 | | 1035 | 1057 | | 1218 | 1450 | 1035 |
| Date | 4/23/98 | 4/23/98 | 4/23/98 | 4/23/98 | 4/23/98 | 4/23/98 | 4/22/98 | 4/22/98 | 4/22/98 | 4/22/98 | 4/21/98 | 4/22/98 | $\overline{}$ | | | 4/24/98 | 4/24/98 | 4/29/98 | 4/28/98 | 4/22/98 | 4/22/98 |
| Depth | 0-1. | 0-1' | 0-1, | 0-1, | 0-1. | 0-1. | 0-1. | 0-1, | 0-1, | 0-1, | 0-1, | 0-1. | 0-1, | 0-1, | 0-1. | 2-4' | 4-5' | 0-1, | 2-4. | 0-1. | 0-1- |
| г и́е Туре | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | SURF | BORE | BORE | SURF | BORE | SURF | SURF |
| Sample Location | Pad 5 | Pad 6 | Pad 37 | Pad 38 | Pad 40 | Pad 58 | Pad 59 | Pad 60 | Pad 61 | Pad 62 | Pad 66 | Pad 67 | Pad 68 | Pad 68 | Deac. Furnace | Pad 66 | Pad 66 | Pad 66 | Pad 67 | Pad 60 | Pad 68 |
| SAIC Sample ID | WB0691 | E6908M | 96908M | WB0697 | WB0702 | WB0705 | WB0706 | WB0711 | WB0715 | WB0718 | WB0723 | WB0729 | WB0730 | WB0731 | WB0733 | WB0750 | WB0751 | WB0768 | WB0770 | WB0869 | WB0868 |
| Site ID | WBG | WBG | WBG | WBG | WBG | WBG | WBG | WBG | WBG | WBG | WBG | WBG | WBG | WBG | - | WBG | WBG | WBG | WBG | WBG | WBG |

PRUCEDURES FOR ASSESSING PRESIDUAL PRUPELLANT (NITROGLYCERIN)
MITRUCELLULUSE + NITROGUANIDINE)

WERE NOT INCLUDED IN THE DELIVERY ORDER SOW.

SUCH CONTAMINATION IS DETECTED IN THE FIRED SCREENING

TEST FUR RDX. ANDLYTICAL TESTS, IN ADDITION TO CONVENTION

THUS

EXPLOSIVE TESTS, ARE TO BE CONDUCTED ON:

- ANY SURFACE OR SUBSURFACE SOMPLE THAT HAS A FIELD SCOREN

 DETECT FUR TINT IR RDX. (FOR NATURE + EXTERT PURPUSES)
- AT LEAST ONE (1) SURFACE SAMPLE FROM TEACH OF 14 PASS (FUR OA + RISK ASSESSMENT PURPUSIES, ALLO
- OH EACH GRUNDWATTER SAMPLE FROM THE WITHCHEFICKE

 FIVE(S) NEW WELLS + FOUR(U) EXSTINC RCRA WELLS +

 OHE(I) QA (FOR EXTENT + RISK ASSESSMENT PURPOSES)

| FIELD Change Order (FCO) |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| MODIFICATION NO DATE 5/6/98 WORK AUTHORIZATION |
| TYPE OF CHANGE PRIORITY OFMERGENCY OF THE CONTINUE |
| ADS NO CYWP NO CWBS NO O MINOR O MAJOR O OTHER |
| |
| NAME MIKE KINDERS ORGANIZATION SAIC PHONEPHONE |
| TITLE FIELD DES MANAGERSIGNATURE |
| BASELINE IDENTIFICATION |
| BASELINE(S) AFFECTED O COST O SCOPE O MILESTONES O METHOD OF ACCOMPLISHMENT |
| PROGRAM SERVICE ORDER NO REVISION NO CAM SIGNATURE |
| DESCRIPTION OF CHANGE |
| PHONE 12 JE CONTINUENCY STAMPLES SURFACE AND SUBSURFACE SOIL SAMPLES WE SCOPED FOR WBC PAOS MECHOCO IN (AS DESCRIBED IN THE SAP ADDIENOUM) WILL INSTEAD BE COLLECTED FROM WBC PAO 70 AT 2 SAMPLING LUCATIONS AT PAO 70 SAMPLES WILL BE COLLECTED FROM O-1 AND 2-4 FT AND MURLYZED FOR METALS & EMPLUSIVES AT 3 OTHER LOCATIONS SAMPLES WILL BE COLLECTED FROM QUI AND 2-4 AND |
| SAP ADDIENOUM) WILL INSTEAD BE COLLEGED IN THE |
| AT 2 SAMPLING LUCATIONS AT PAD 70 SAMPLES WILL BE COLLECTED FROM |
| JUSTIFICATION ANDLY SED FOR YOUR WESTER FROM O-1 AND 2-4 AND |
| JUSTIFICATION ANALYZED FOR VOCS INSTEAD OF TAL AND SVOCS INSTEAD OF EXP. AT 2 OF THESE SAME 3 LOCATIONS, SAMPLES WILL ADDITIONALLY BE COLLECTED FROM H-C AND LIKEWISE BANALYZED FOR VOCS AND SJOC INSTEAD OF TALL EXP. |
| SUC INSTEAD OF TALL EXP |
| |
| JUSTIFICATION: 13 CONTINUENCY SAMPLES WERE NOT USED AT OTHER PAOS BECAUSIE OF QUAINTITY OF SCREENING NOW- DETECTS. SAMPLES ARE TO BE CONTECTED AT PAO TO OVE TO THE PRESENCE OF SUPPECT MINTERIALS OBSERVED AT PAO TO VOCS + SUOCS ARE TO BE ANALYZED INSTEAD OF |
| OBSERVED AT PAD 70. VOCS + SVOCS ARE TO BE AMALYZED INSTEAD OF THE LEXP IN SELECT SAMPLES DUE TO THE OBSERVANCE |
| MPACT OF NOT IMPLEMENTING REQUEST OF HYDROCARBON GOORS. |
| - CONTIGENCY SAMPLES WOULD GO UNUSED ARED POTENTIAL |
| CONTISMINISTION AT PAD 70 WOULD REMAIN UNINVESTIGATED. |
| |
| |
| PARTICIPANTS AFFECTED BY IMPLEMENTING REQUEST |
| FIELD TEAM, LABORATORY, DATA VALIDATORS, |
| DATA USELS |
| , , |
| |
| COST ESTIMATE \$ 300.00 ESTIMATOR SIGNATURE |
| CHIPO) AND RIP MANAYSIS (HS) X P. VOC & PHONE (GIS) 8678548 DATE 5/6/98 |
| PREVIOUS FC AFFECTED O YES O NO |
| APPROVAL |
| PROJECT MANAGER SIGNATURE DATE 5/6/98 |
| QAS REVIEW DATE |
| TIME FROM INITIATION TO ACTION |
| The state of the Action |
| D-23 |

| FIELD Change Order (FCO) |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| MODIFICATION NO DATE $05/07/98$ WORK AUTHORIZATION |
| TYPE OF CHANGE PRIORITY O EMERGENCY O LIBORATE O BOLIFING |
| ADS NO CYWP NO CWBS NO O MINOR O MAJOR O OTHE |
| THE GOEST EN IDENTIFICATION |
| NAME MIXE KLIDEES ORGANIZATION SAIC PHONE (615)867-3546 |
| TITLE FIELD OPS MANAGER SIGNATURE MULLIAN |
| BASELINE IDENTIFICATION |
| BASELINE(S) AFFECTED COST SCOPE O MILESTONES O METHOD OF ACCOMPLISHMENT |
| PROGRAM SERVICE ORDER NO. ——————— REVISION NO CAM SIGNATURE |
| DESCRIPTION OF CHANGE AND 3 HOW |
| THE O-1 FT RESASCIL SAMPLES FROM STA. CONTINGENCY STA. WBGSSICB WERE FIELD SCREENED AT FOR EXPLOSIVES AT & VALUES? 1 PPM. AT THE DIRECTION OF THE USACE PROJECT MANAGER (SOHN JENT) A SAMPLE FROM 4-6 FT WILL NOT BE COLLECTED. |
| JUSTIFICATION WATER LEVIELS IN WELLS MEAR UBGSSIGB INDICATE THAT THE WATER TABLE MAY BE ENCOUNTERED WIN THE 4-6 FT INTERNAL |
| MPACT OF NOT IMPLEMENTING REQUEST |
| SAMPLE MIGHT BE COLLECTED FROM THE SATURATED EDWE WHICH WOULD MAKE THE USEFULLNESS OF THE DATA QUESTIONIBLE |
| |
| PARTICIPANTS AFFECTED BY IMPLEMENTING REQUEST |
| FIELD SAMPLING TEAM, DATA USERS |
| |
| COST ESTIMATE \$ 180.00 ESTIMATOR SIGNATURE W LLAST OF TOPY (105) + CYANIDE (25) PHONE (615)867-3548 DATE 5/7/98 |
| PREVIOUS FC AFFECTED O YES O NO |
| APPROVAL PROJECT MANAGER SIGNATURE DATE 5/7/98 |
| QAS REVIEW DATE |
| TIME FROM INITIATION TO ACTION |
| D-24 |

D-25

| | | 1 |
|--|--|---|