











Military Munitions Response Program (MMRP)

RVAAP RAB Meeting

27 Sep 06

Mary Ellen Maly MMRP Program Manager USAEC







- Response actions (identification, investigation and removal or remedial actions) to address unexploded ordnance (UXO), discarded military munitions (DMM) or the chemical residue of munitions (MC).
- Created by Congress via the 2002 Defense Authorization Act (modified 10 USC 2701)

This is a very new program for Active Installations



Definitions



- Military Munitions -

 All ammunition products except wholly inert items, improvised explosive devices and nuclear weapons









- Unexploded Ordnance (UXO) -
- A Military Munition that has been:
 - Primed, fused, armed or prepared for action;
 - Has been fired, dropped, launched and;
 - Remains unexploded
- UXO are very sensitive, making them very dangerous items





Definitions

- Discarded Military Munitions (DMM) -
- A Military Munition that has been abandoned without proper disposal. Does not include UXO.
- Still dangerous, but generally not as sensitive as UXO.



Definitions



- Munitions Constituents (MC) -
- Any materials originating from UXO or DMM. Includes explosive and nonexplosive materials.



Examples: RDX, HMX, TNT, Lead, Antimony,





Origins of the MMRP

- Army Range Inventory Identified & documented the Army's current and historic military range lands and munitions sites
- Initial Operational Range Inventory
 - Oct 2000 Jan 2003
 - 479 installations / 10,520 ranges / 15,142,989 acres
 - Non-Operational Ranges & UXO Sites Inventory
 - Oct 2001 Dec 2003
 - 183 ER,A Installations / 937 sites / 2,905,650 acres








- The <u>release</u>* occurred prior to 30 Sep 2002
- The site is not on an operational range
- The site is not on a permitted munitions disposal facility
- Non-Operational Range Inventory Eligibility Results
 - IRP: 30 installations / 98 sites / 4,683 acres
 - MMRP: 166 installations / 819 sites / 2,899,437 acres
 - Non-DERP: 18 installations / 34 sites / 1,530 acres


^{*} Release = For munitions, means shooting, firing or placement











MMRP At RVAAP – Inventory Results



Blue text means the site is no longer MMRP eligible

Site Name	Size (acres)	Туре
Ramsdell Quarry Landfill	4	Disposal
Erie Burning Ground	34	Burning, Disposal
Demolition Area #2	15	Detonation
Winklepeck Burning Ground	317	Burning, Disposal
Load Line #1	164	Disposal
Load Line #2	78	Disposal, Burial
Fuze & Booster Quarry	13	Disposal
Landfill North of Wicklepeck	8	Disposal
40mm Firing Range	5	Range
Firestone Test Facility	0.25	Range
Sand Creek Dump	1	Landfill
Buildings F-15 & F-16	12	Disposal
Anchor Test Area	3	Range
Atlas Scrap Yard	66	Disposal
Block D Igloo & Transferred portion	641	Explosion
Water Works #4 Dump	6	Disposal
Area Between Buildings 846 & 849	3	Disposal
Field at the NE Corner of Intersection	92	Disposal









- Complete all <u>Preliminary Assessments</u> by 2007
- Complete all <u>Site Inspections</u> by 2010
- Complete all <u>Cleanups</u> by 2024 (Army Goal), total cost estimated at \$4.7B
- Funding to meet goals:
 - FY06 \$19M FY07 \$35M FY08 \$46M
 - FY09 \$143M FY10 \$229M





Funding Strategy & Priorities



- (1) Complete Site Inspections
- (2) Address imminent threats to human health
- (3) Assist in property transfer at Excess Property Installations
- (4) Conduct follow-on studies & cleanups





MMRP Site Inspections

- Goal of a CERCLA Site Inspection: Collect appropriate amount of data to be able to determine next step (further investigation, interim action or no further action), includes:
 - Presence or absence of contaminants
 - Identification of imminent threats to human health
- Goal of MMRP SI: Same as above, plus:
 - Complete Prioritization Protocol for each site in draft
 - Collect data to assist in fine-tuning the Cost-To-Complete estimate for site
- MMRP SI Addresses:
 - Explosive hazards (UXO & DMM)
 - Munitions Constituent (MC) contamination







Stakeholder Involvement	 Kick-off meeting Identification & inclusion of stakeholders
Historical Records Review (HRR)	 Archives/records searches Personnel interviews
Field Effort	 HRR Report Work Plans Geophysical Work (UXO/DMM)
	Media sampling (MC)
Documentation	Analysis of resultsSI Report w/recommendations



RVAAP Site Inspection Schedule



Kickoff meeting

Draft HRR document

HRR Meeting

Final HRR document

Draft Field Workplan

Final Field Workplan

Field work

Draft SI Report

SI Report Meeting

Final SI Report

October 05 🖈

May 06 🖈



August 06 *

October 06

December 06

February 07

April 07

May 07

August 07

October 07



Activity has already occurred





QUESTIONS?

